

J & R Construction

Phone: (910) 712-0936 | Created: 2026-06-29 12:41 AM

Owned and operated by Jacob Cosentino

ESTIMATE EST-JRC-JOB-315-LILY-FENCE-001

Job Document ID: JRC-JOB-315-LILY-FENCE

Customer: Lily

Job: Lily / 315 Sassafras — Chain-Link Fence

Address: 315 Sassafras Lane

Estimate — Chain-Link Fence (Friends & Family Rate)

Scope of Work

Install chain-link fence at 315 Sassafras Lane per this estimate.

Fence specification:

- Approximately 185 linear feet of 4 ft height galvanized chain-link fence (confirm exact footage on site).
- Line posts, terminal posts, corner/brace posts as required for a standard residential installation.
- Top rail and tension wire as needed for a clean, secure installation.
- Ties, fasteners, concrete for posts, and standard install materials included.
- Layout, post setting, fabric stretch, and final securement.
- Standard walk-gate openings prepared for the two gates listed below.
- Jobsite cleanup of construction debris related to this fence scope.

Gates included in this estimate:

- Gate 1: One (1) four-foot (4 ft) walk gate with standard hinge, latch, and gate hardware.
- Gate 2: One (1) four-foot (4 ft) walk gate with standard hinge, latch, and gate hardware.
- Total gates: Two (2) four-foot (4 ft) gates.
- This estimate does NOT include an eight-foot (8 ft) gate, double-wide gate, or vehicle gate.

Customer-facing line items:

- Materials: chain-link fabric, posts, rails, concrete, ties, gate frames, and hardware — \$2,850.00
- Labor: layout, post setting, fence run install, and two (4 ft) gate installs — \$5,475.00
- Standard fence price — \$8,325.00
- Friends & Family Discount — -\$1,125.00
- Friends & family price — \$7,200.00

This estimate covers the fence scope above only. Stair work at this property is billed on separate invoices.

Standard Price	\$8,325.00
Friends & Family Discount	-\$1,125.00
Friends & Family Price	\$7,200.00
Deposit Due Before Work Begins	\$3,600.00
Balance Due Upon Completion	\$3,600.00

Discount Note

Friends & family best price applied. This reduced rate reflects our relationship and the combined work planned at 315 Sassafras Lane.

Payment Terms

50% deposit due before work begins. Remaining 50% balance due upon completion unless otherwise noted in writing.

Notes / Exclusions

Price may change if hidden damage, rot, rock, roots, drainage issues, utility conflicts, property-line disputes, code issues, unsafe conditions, or additional required work is discovered after layout or during installation. Final linear

footage, post spacing, gate locations, and terminal points will be confirmed on site before work begins. Painting, staining, clearing/grading beyond normal fence-line cleanup, and optional add-ons are excluded unless specifically included. This fence estimate is separate from the stair invoices for this property.

Customer-facing copy. Internal cost sheets, helper payment notes, and tax/profit notes are excluded by J&R standard.