

J & R Construction

Phone: (910) 712-0936 | Created: 2026-06-28 11:05 PM

Owned and operated by Jacob Cosentino

ESTIMATE EST-JRC-JOB-315-LILY-STAIR-SET-01-001

Job Document ID: JRC-JOB-315-LILY-STAIR-SET-01

Customer: Lily

Job: Lily / 315 Sassafras — Stair Set 1

Address: 315 Sassafras Lane

Estimate — Stair Set 1 Rebuild

Scope of Work

Stair Set 1 — First stair set at 315 Sassafras Lane (location to be marked on site)

Rebuild one exterior stair set per this quote using the following specification:

- Approximately 4 ft clear tread width (confirm exact width on site).
- Pressure-treated 2x6 treads.
- Pressure-treated 1x8 kickplates / riser boards.
- Three (3) housed / pocket-cut stringers laid out and cut on site.
- Stair assembly framed, leveled, and secured to existing structure or approved landing points.
- 2x4 handrail installed along the stair run per standard safe handhold height.
- Work performed by owner/operator working solo, including stringer layout and cutting.
- Jobsite cleanup of construction debris related to this stair set.

Customer-facing line items:

- Materials: pressure-treated lumber, fasteners, anchors, and related install supplies — \$650.00
- Labor: layout, pocket stringer cutting, framing, tread/kickplate install, handrail (solo) — \$1,750.00

This quote covers only the stair set described above. The second stair set at 315 Sassafras Lane is quoted separately.

Total Customer Price	\$2,400.00
Deposit Due Before Work Begins	\$1,200.00
Balance Due Upon Completion	\$1,200.00

Payment Terms

50% deposit due before work begins. Remaining 50% balance due upon completion unless otherwise noted in writing.

Notes / Exclusions

Price may change if hidden damage, rot, structural issues, code issues, unsafe conditions, or additional required work is discovered after opening up the work area. Painting, staining, and optional add-ons are excluded unless specifically included. Final tread count and total rise will be confirmed on site before work begins; this quote assumes a standard residential exterior stair height unless field conditions require adjustment.

Customer-facing copy. Internal cost sheets, helper payment notes, and tax/profit notes are excluded by J&R standard.